

Subdivisional Lines, T 6 N R 31 E W M.

| Chains | notes of Resurvey of Exterior Bdys. of T 5 N R 31 E.) |
|--------|---|
| | Therefore S.88°34' W. on true line bet. Secs. 25 & 36. |
| 40.50 | Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor. |
| 81.00 | The Cor. to Secs. 25, 26, 35 & 36. Land; hilly. Soil; good. |
| | N. bet. Secs. 25 & 26. Var.21°30' E. |
| 40.00 | Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor. |
| 80.00 | Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. of Secs. 23, 24, 25 & 26. Drove pine stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; good. |
| | E. on random bet. Secs. 24 & 25. |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. |
| 81.60 | Intersect E. Bdy. of Tp., 278 lks. S. of Cor. S.88°01' W. on true line. |
| 40.80 | Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor. |
| 81.60 | The Cor. Land; rolling. Soil; 1st rate. |
| | N. bet. Secs. 23 & 24. Var.21°30' E. |
| 40.00 | Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor. |
| 80.00 | Drove charred stake & raised mound of earth, with pits, etc., |