

Subdivisional Lines, T 6 N R 31 E W M.

Chains

- 40.00 Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
- 42.50 Intersect State Bdy. line, 892 lks. W. of the 4 Mile Cor.
Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Closing Cor. to frac. Secs. 14 and 13. Drove pine stake, 2 ft. long, 2 ins. sq., in E. pit.
- Land; rolling.
- Soil; good.
- Note:
The E. Bdy. of Sec. 13 is 39.15 chs. in length. Remeasured also 5th Mile on State Bdy. line and find it to be 80.60 chs. in length.

Nov. 13, 1874.

N. bet. Secs. 34 & 35.

- 40.00 Set basalt stone, 20 x 8 x 5, 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor.
- 41.00 Bed of Juniper Canyon, course W.
- 80.00 Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 26, 27, 34 & 35.
Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit.
- Land; hilly.
- Soil; 2nd rate.

E. on random line bet. Secs. 26 & 35.

- 40.00 Set temp. $\frac{1}{4}$ Sec. Cor.
- 80.46 Intersect N. & S. line, 35 lks. S. of Cor.
S. 89°45' W. on true line.
- 40.23 Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
- 80.46 The Cor.
- Land; rolling.
- Soil; good.
- Grass; good.