

Subdivisional Lines, T 6 N R 31 E W M.

Chains	
	N. bet. Secs. 32 & 33.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
65.00	Juniper Canyon, course W.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 28, 29, 32 & 33. Drove pine stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; hilly. Soil; 2nd rate.
<hr/>	
	E. on random line bet. Secs. 28 & 33.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
81.26	Intersect N. & S. line, 18 lks. S. of Cor. S. 89°52' W. on true line.
21.25	Ravine, course S.
40.63	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
81.26	The Cor. Land; hilly. Soil; good. Grass; good. Note: The S. Bdy. of Sec. 33 is 81.24 chs. in length (See field notes of Exterior Bdys. T 5 N R 31 E, the N. Bdy. of Sec. 4.)
<hr/>	
	N. bet. Secs. 28 & 29. Var. 22° E.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 20, 21, 28 & 29. Drove pine stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; good.