

Subdivisional Lines, T 6 N R 31 E W M.

Chains	E. on random line bet. Secs. 21 & 28.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
81.20	Intersect N. & S. line at Cor. W. on true line.
40.60	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
81.20	The Cor. Land; rolling. Soil; 1st rate.
	Nov. 16th, 1874.
	N. bet. Secs. 20 & 21. Var. 21°45' E.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 16, 17, 20 & 21. Drove pine stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; good.
	E. on random line bet. Secs. 16 & 21.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
81.40	Intersect N. & S. line, 40 lks. S. of Cor. S. 89° 43' W. on true line.
40.70	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
81.40	The Cor. Land; gently rolling. Soil; good.
	N. bet. Secs. 16 & 17. Var. 21°30' E.
40.00	Drove charred stake & raised mound of earth, with pits, etc.