

## Subdivisional Lines, T 6 N R 31 E W M.

Chains	as per instructions.
44.00	Intersect State Bdy. line, 964 lks. W. of 1st Mile Cor. Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to frac. Secs. 16 & 17. Drove pine stake, 2 ft. long, 2 ins. sq., in E. pit. Land; gently rolling. Soil; good.
	N. bet. Secs. 31 & 32.
1.25	Leave Juniper Canyon ; ascend hill brs. N.E. & S.W.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor. Top of hill brs. N.E. & S.W.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 29, 30, 31 & 32. Drove pine stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; S. $\frac{1}{2}$ , hillside sloping S.E.- N. $\frac{1}{2}$ gently rolling. Soil; 2nd rate.
	E. on random line bet. Secs. 29 & 32.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
73.82	Intersect N. & S. line, 841 lks. N. of Cor. N. 83° 30' W. on true line bet. Secs. 29 & 32.
37.15	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
74.30	The Cor. Land; rolling. Soil; good. Note: The Cor. to Secs. 31 & 32, on S. Bdy. of Tp. stands 73.29 chs. W. and 884 lks. N. of Cor. to Secs. 32 & 33 on S. Bdy. ( See field notes of Resurvey of Exterior Bdys. T 5 N. R 31 E, the N. Bdy. of Sec. 5.) In the line above the distance, 74.30 chs. on the true line corresponds with the distance, 73.82 chs. on the random line