

Subdivisional Lines, T 6 N R 32 E W M.

Chains	<p>1ks. W. of 10 mile Cor.</p> <p>Set basalt stone, 18 x 10 x 9, 9 ins. in ground, for Closing Cor. to frac. Secs. 13 & 14.</p> <p>Land; slopes gently to N.</p> <p>Soil; good.</p> <p style="text-align: right;">Nov. 20th, 1874.</p>
40.00	<p>N. bet. Secs. 34 & 35.</p> <p>Deposit basalt stone, 5 x 4 x 3, marked with a cross (X) and raised mound of earth with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.</p>
80.00	<p>Set basalt stone, 14 x 12 x 5, 17 ins. in ground, for Cor. to Secs. 26, 27, 34 & 35.</p> <p>Land; gently rolling.</p> <p>Soil; good.</p>
40.00	<p>E. on random line bet. Secs. 26 & 35.</p> <p>Set temp. $\frac{1}{4}$ Sec. Cor.</p>
80.90	<p>Intersect N. & S. line, 35 lks. S. of Cor.</p> <p>S. 89°45' W. on true line.</p>
40.45	<p>Deposit basalt stone, 5 x 4 x 4, marked with a cross (X), and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.</p>
80.90	<p>The Cor.</p> <p>Land; gently rolling.</p> <p>Soil; good.</p>
40.00	<p>N. bet. Secs. 26 & 27.</p> <p style="text-align: right;">Var. 21°00' E.</p> <p>Deposit basalt stone, 5 x 4 x 2, marked with a cross (X) and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.</p>
80.00	<p>Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 22, 23, 26 & 27.</p>