

Subdivisional Lines, T 6 N R 32 E W M.

Chains	<p>Drove pine stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; gently rolling. Soil; good.</p>
	<p>E. on random line bet. Secs. 23 & 26:</p>
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.25	Intersect N. & S. line, 30 lks. S. of Cor. S.89°47' W. on true line.
40.12	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.25	The Cor. Land; gently rolling. Soil; good.
	<p>N. bet. Secs. 22 & 23. Var.20°30' E.</p>
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 14, 15, 22 & 23. Drove pine stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; gently rolling. Soil; good.
	<p>E. on random line bet. Secs. 14 & 23.</p>
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.50	Intersect N. & S. line, at Cor. W. on true line.
40.25	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
46.00	Wagon road, in ravine, course W.
80.50	The Cor. Land; hilly, sloping to ravine., Soil; 2nd rate. Grass; good.