

## Subdivisional Lines, T 6 N R 32 E W M.

## Chains

N. bet. Secs. 14 & 15.

Var. 22°00' E.

40.00 Set basalt stone, 16 x 8 x 6, 8 ins. in ground, for  $\frac{1}{4}$  Sec. Cor.

40.42 Intersect Bdy. line bet. Oregon & Washington Territory, 697 lks. W. of 9 Mile Cor., in canyon running W.

Set basalt stone, 18 x 14 x 12, 9 ins. in ground, for Closing Cor. to frac. Secs. 14 & 15.

Land; hilly.

Soil; 2nd rate.

N. bet. Secs. 33 & 34.

40.00 Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for  $\frac{1}{4}$  Sec. Cor.

80.00 Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 27, 28, 33 & 34.

Drove willow stake, 2 ft. long, 2 ins. sq. in S.E. pit.

Land; gently rolling.

Soil; 1st rate.

E. on random line bet. Secs. 27 & 34.

40.00 Set temp.  $\frac{1}{4}$  Sec. Cor.

81.30 Intersect N. & S. line at Cor.

W. on true line.

40.65 Deposit basalt stone, 6 x 5 x 4 and raised mound of earth, with pits, etc., as per instructions, for  $\frac{1}{4}$  Sec. Cor.

81.30 The Cor.

Land; gently rolling.

Soil; good.

## Note:

The resurvey of the S. Bdy. of Sec. 34 shows that line to be 81.29 chs. (See Resurvey of N. Bdy. of T 5 N R 32 E Sec. 3.)