

Subdivisional Lines, T 6 N R 32 E W M.

Chains

Drove pine stake, 2 ft. long, 2 ins. sq., in S.E. pit.
 Land; gently rolling.
 Soil; 1st rate.

E. on random line bet. Secs. 16 & 21.

40.00 Set temp. $\frac{1}{4}$ Sec. Cor.

80.85 Intersect N. & S. line, 21 lks. N. of Cor.
 N.89°51' W. on true line.

40.48 Drove charred stake & raised mound of earth, with pits, etc.,
 as per instructions, for $\frac{1}{4}$ Sec. Cor.

80.85 The Cor.

Land; rolling.

Soil; good.

Grass; good.

N. bet. Secs. 16 & 17.

Var. 21°30' E.

39.69 Intersect Bdy. line bet. Oregon & Washington Territory,
 928 lks. W. of 7 Mile Cor.

Set basalt stone, 18 x 10 x 8, for Closing Cor. to frac.
 Secs. 16 & 17.

Land; rolling.

Soil; good.

Nov. 22d, 1874.

N. bet. Secs. 31 & 32.

40.00 Drove charred stake & raised mound of earth, with pits, etc.,
 as per instructions, for $\frac{1}{4}$ Sec. Cor.

80.00 Drove charred stake & raised mound of earth, with pits, etc.,
 as per instructions, for Cor. to Secs. 29, 30, 31 & 32.

Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit.

Land; rolling.

Soil; good.

Grass; good.