

Subdivisional Lines, T 6 N R 32 E W M.

Chains	E. on random line bet. Secs. 17 & 20.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.80	Intersect N. & S. line, 16 lks. S. of Cor. S.89°53' W. on true line.
40.40	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.80	The Cor. Land; gently rolling. Soil; good.
<hr/>	
	W. on random line bet. Secs. 18 & 19.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.50	Intersect W. Boundary, 126 lks. S. of Cor. S.89°06' E. on true line.
39.50	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
79.50	The Cor. Land; rolling. Soil; good. Grass; good.
	Note: The W. Bdy. of Secs. 19 is 80.94 chs. in length and bears 60 lks. E. of N. (See Resurvey of E. Bdy. of Secs. 24, pg. 5, subdivisions of T 6 N R 31 E.)
<hr/>	
	N. bet. Secs. 17 & 18. Var. 21°30' E.
40.00	Intersect Bdy. line bet. Oregon & Washington Territory, 1032 lks. W. of 6 Mile Cor. Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Closing Cor. to fractional Secs. 18 & 19. Drove pine stake, 2 ft. long, 2 ins. sq., in E. pit. Land; gently rolling. Soil; 1st rate. Grass; good. Nov. 23d, 1874.