

Subdivisional Lines, T 6 N R 33 E W M.

Chains	N. bet. Sees. 23 & 24.
	Var. 21°00'E.
40.00	Set alder post, 4 ft. long, 3 ins. diam.; drove charred stake & raised mound, with pits, etc., as per instructions for $\frac{1}{4}$ Sec. Cor.
80.00	Set alder post, 4 ft. long, 3 ins. sq.; drove charred stake; raised mound of earth, with pits, etc., as per instructions, for Cor. to Sees. 13, 14, 23 & 24.
	Land; gently rolling.
	Soil; 1st rate.
	E. on random line bet. Sees. 13 & 24.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.50	Intersect E. Bdy. of Tp., 245 lks. S. of Cor. S. 88°15' W. on true line.
39.75	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
79.50	The Cor.
	Land; gently rolling.
	Soil; 1st rate.
	N. bet. Sees. 13 & 14.
	Var. 21°00' E.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
65.09	Intersect Bdy. line bet. Oregon & Washington Territory, 910 lks. W. of the 16 Mile Cor. Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Closing Cor. to fractional Sees. 13 & 14.
	Drove pine stake, 2 ft. long, 2 ins. sq., in E. pit.
	Land; gently rolling.
	Soil; good.
	N. bet. Sees. 34 & 35.
40.00	Set alder post, 4 ft. long, 3 ins. diam.; drove charred