

Subdivisional Lines, T 6 N R 33 E W M.

| Chains | |
|--------|---|
| | E. on random line bet. Sess. 23 & 26. |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. |
| 79.89 | Intersect N. & S. line, 2596 lks. N. of Cor. N.72°00' W. on true line. |
| 24.00 | Ravine, course N.W. |
| 42.00 | Set basalt stone, 12 x 10 x 9, 6 ins. in ground, for $\frac{1}{4}$ Sec. Cor. |
| 84.00 | The Cor. Land; hilly. Soil; 2nd rate. Nov. 25th, 1874. |
| | N. bet. Sess. 22 & 23. Var. 21°30' E. |
| 40.00 | Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor. |
| 80.00 | Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Sess. 14, 15, 22 & 23. Land; rolling. Soil; good. |
| | E. on random line bet. Sess. 14 & 23. |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. |
| 79.47 | Intersect N. & S. line, 2621 lks. N. of Cor. N.71°45' W. on true line. |
| 32.00 | Ravine, course N. |
| 41.84 | Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor. |
| 83.68 | The Cor. Land; gently rolling. Soil; good. |
| | N. bet. Sess. 14 & 15. Var. 21°00' E. |