

Subdivisional Lines, T 6 N R 33 E W M.

Chains	
39.90	Set basalt stone, 18 x 12 x 6, 9 ins. in ground, for $\frac{1}{4}$ Sec. Cor.
79.80	The Cor. Land; rolling. Soil: good.
N. bet. Secs. 27 & 28. Var. 20°30' E.	
40.00	Set basalt stone, 12 x 10 x 9, 6 ins. in ground, for $\frac{1}{4}$ Sec. Cor.
80.00	Set basalt stone, 12 x 10 x 5, 6 ins. in ground, for Cor. to Secs. 21, 22, 27 & 28. Land; rolling. Soil; good.
E. on random line bet. Secs. 22 & 27.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.30	Intersect N. & S. line, 170 lks. S. of the Cor. S. 88°47' W. on true line.
39.65	Set basalt stone, 16 x 8 x 5, 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor.
79.30	The Cor. Land; rolling. Soil; 2nd rate.
N. bet. Secs. 21 & 22. Var. 23°30' E.	
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set basalt stone, 16 x 9 x 7, 8 ins. in ground, for Cor. to Secs. 15, 16, 21 & 22. Land; rolling. Soil; good.