

East Boundary, T 6 N R 34 E W M.,
 As surveyed by William H. Odell, U.S. Dept. Surveyor,
 Under Contract No. 110,
 Dated Feby. 7th, 1865.

Chains	
	N. on E. Bdy. of Sec. 36.
	Var. 21° E.
37.75	Sod fence, course E. & W.
40.00	Set $\frac{1}{4}$ Sec. post, on level. Drove charred stake; dug pits; raised mound, as per instructions.
59.25	Sod fence, course E. & W.
64.22	Dry creek, 25 lks. wide, course W.
80.00	Set post Cor. for Secs. 25, 36, 31 & 30. Drove charred stake; dug pits & raised mound, as per instructions.
	Land; rolling.
	Grass; good.
	Soil; in field, 1st rate.
	N. on E. Bdy. of Sec. 25.
	Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post on level. Drove charred stake; dug pits & raised mound, as per instructions.
50.00	Cross road, course N.E.
51.68	Leave spring branch, course W.
80.00	Set post Cor. for Secs. 24, 25, 19 & 30. Drove charred stake; dug pits & raised mound, as per instructions.
	Land; level.
	Grass; good.
	Soil; 2nd rate.
	N. on E. Bdy. of Sec. 24.
	Var. 21° E.
28.20	Road, course W.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 13, 24, 18 & 19. Drove charred stake; dug pits & raised mound, as per instructions.
	Land; gently rolling.
	Grass; good.
	Soil; good 2nd rate.