

## Subdivisional Lines, T 6 N R 34 E W M.

Chains	E. on random bet. Secs. 22 & 27.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.10	Intersect N. & S. line, 15 lks. S. of post, from which, I run S. 89° 54' W. on true line.
40.05	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
80.10	To post Cor. Land; rolling. Grass; good. Soil; 2nd rate.
<hr/>	
	N. bet. Secs. 21 & 22. Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 15, 16, 21 & 22. Drove charred stake; dug pits & raised mound, as per instructions. Land; rolling. Soil; 2nd rate. Grass; good.
<hr/>	
	E. on random bet. Secs. 15 & 22.
35.00	Ditch fence.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.20	Intersect N. & S. line, 12 lks. S. of post, from which, I run S. 89° 55' W. on true line.
40.10	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
80.20	To post Cor. Land; broken. Soil; 2nd rate.
<hr/>	
	N. bet. Secs. 15 & 16. Var. 21° E.