

Subdivisional Lines, T 6 N R 34 E W M.

Chains	
9.50	Enter field.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
52.45	Intersect State Bdy., 9.30 chs. W. of 20th Mile post. Set post Cor. for Secs. 15 & 16. Drove charred stake; dug pits & raised mound, as per instructions. Land; level. Soil; good 2nd rate.
<hr/>	
	N. bet. Secs. 32 & 33. Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 28, 29, 32 & 33, on hillside, sloping to N. Drove charred stake; dug pits & raised mound, as per instructions. Land; broken. Grass; good. Soil; 2nd rate.
<hr/>	
	E. on random bet. Secs. 28 & 33.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.92	Intersect N. & S: line, 40 lks. S. of post, from which, I run S. 89°43' W. on true line.
39.96	Set $\frac{1}{4}$ Sec. post Cor., on land sloping E. Drove charred stake dug pits & raised mound, as per instructions.
79.92	To post Cor. Land; broken. Soil; 2nd rate.
<hr/>	
	N. bet. Secs. 28 & 29. Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised