

Subdivisional Lines, T 6 N R 34 E W M.

Chains

40.12 Set 1/4 Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

80.25 To post Cor.
Land; rolling.
Grass; good.
Soil; 2nd rate.

N. bet. Secs. 16 & 17.

Var.21° E.

9.50 Pine Creek, course N.W.

32.00 Fence, course S. & W.

40.00 Set 1/4 Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.

52.83 To State Bdy. line, 9.35 chs. W. of 19th Mile post.
Set post Cor. for fractional Secs. 16 & 17. Drove charred stake; dug pits & raised mound, as per instructions.

N. bet. Secs. 31 & 32.

Var.21° E.

40.00 Set 1/4 Sec. post Cor., on land slopes to N.; dug pits & raised mound, as per instructions.

80.00 Set post Cor. for Secs. 29, 30, 31 & 32.
Land slopes to N.W. Drove charred stake; dug pits & raised mound, as per instructions.
Land; broken.
Grass; good.
Soil; 2nd rate.

E. on random bet. Secs. 29 & 32.

40.00 Set temp. 1/4 Sec. post Cor.

79.86 Intersect N. & S. line, 30 lks. S. of post, from which,
I run
S.89°47' W. on true line.

39.83 Set 1/4 Sec. post Cor. Land slopes to N.W. Drove charred stake; dug pits & raised mound, as per instructions.