

## Subdivisional Lines, T 6 N R 34 E W M.

Chains	
79.66	To post Cor. Land; rolling. Grass; good. Soil; 2nd rate.
<hr/>	
	W. on random bet. Sees. 30 & 31.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor. post.
78.65	Intersect W. Tp. line, 24 lks. S. of post, from which, I run S.89° 50' E. on true line.
38.65	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
88.65	To post Cor. Land; rolling. Grass; good. Soil; 2nd rate.
<hr/>	
	N. bet. Sees. 29 & 30.  Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Sees. 19, 20, 29 & 30. Drove charred stake; dug pits; raised mound, as per instructions. Land; rolling. Grass; good. Soil; 2nd rate.
<hr/>	
	E. on random bet. Sees. 20 & 29.
40.00	Set Temp. $\frac{1}{4}$ Sec. post Cor.
79.81	Intersect N. & S. line, 15 lks. S. of post, from which, I run S.89°54' W. on true line.
39.90	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.
79.81	To post Cor. Land; rolling. Grass; good. Soil; 2nd rate.