

Subdivisional Lines, T 6 N R 34 E W M.

Chains	W. on random bet. Secs. 18 & 19.
27.80	Trail, course nearly E. & W.
40.00	Set temp. $\frac{1}{4}$ Sec. post
78.91	Intersect W. Tp. line, 43 lks. S. of post, from which, I run S.89°42' E. on true line.
38.91	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
78.91	To post Cor. Land; gently rolling. Grass; good. Soil; 2nd rate.
N. bet. Secs. 17 & 18.	
Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.
53.12	To State Bdy. line, 9.54 shs. W. of 18th Mile post. Set post Cor. for Secs. 17 & 18. Drove charred stake; dug pits & raised mound, as per instructions. Land; gently rolling. Grass; good. Soil; 2nd rate.
<u>General Description.</u>	
<p>This Tp. embraces some of the best lands in Walla Walla Valley, what is known as the Hudson's Bay Farm is in the Northern portion of the Tp. This farm is very valuable for the hay that it produces. There are several other valuable places along Dry Creek, above the junction of Pine Creek, also some good land on Pine Creek. All the lands not adapted to cultivation are valuable for pasturage.</p>	