

Exterior Bdy., T 6 N R 35 E W M.

Chains	N. on E. Bdy. of Sec. 13.
	Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post on level. Drove charred stake; dug pits & raised mound, as per instructions.
53.00	Intersect State Line, 16 chs. & 22 lks. W. of Bdy. Post marked 29 M. on W. side, 46° L 1864 on E. side.
	Set post Cor. for fractional Secs. 13 & 18. Drove charred stake; dug pits & raised mound, as per instructions.
	Land; level.
	Soil; 1st rate.
Subdivisional Lines, T 6 N R 35 E W M. As surveyed by same Surveyors, Under same Contract & date.	
	H
	N. bet. Secs. 35 & 36.
	Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post, on level. Drove charred stake and raised mound of stone, as per instructions.
80.00	Set post Cor. for Secs. 25, 26, 35 & 36, on level. Drove charred stake & raised mound of stones, as per instruct.
	Land; level.
	Soil; quite gravelly.
	H
	E. on random bet. Secs. 25 & 36.
28.00	Road, course N.
30.10	Creek, 10 lks. wide, course N.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
42.30	Creek, 20 lks. wide, course N.
45.40	Enter Mr. Lord's field, course of fence N.
79.25	Leave field.
80.05	Intersect E. Tp. line, 22 lks. N. of post Cor., from which
	I run
	N. 89° 51' W. on true line.
40.02	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake and raised mound of stone, as per instructions.