

## Subdivisional Lines, T 6 N R 35 E W M.

Chains	
27 M.	Set post Cor. for fractional Secs. 14 & 15. Drove charred stake; dug pits & raised mound, as per instructions. Land; level. Soil; 2nd rate.
N. bet. Secs. 33 & 34.	Var. 21°E.
40.00	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.
51.90	Road, course N.W.
80.00	Set post Cor. for Secs. 27, 28, 33 & 34. Drove charred stake; dug pits & raised mound/ <sup>of stone</sup> as per instructions. Land; level. Grass; good. Soil; 2nd rate.
E. on random bet. Secs. 27 & 34.	40.00
Set temp. $\frac{1}{4}$ Sec. post.	79.68
Intersect N. & S. line, 20 lks. S. of post, from which, I run S. 89° 51' W. on true line.	39.84
Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.	79.84
To post Cor.	Land; level.
Soil; gravelly.	N. bet. Secs. 27 & 28.
Var. 21°E.	40.00
Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.	63.75
Spring branch, 4 lks., course N.W.	89.44
Creek, 15 lks. wide, course N.W.	