

Subdivisional Lines, T 6 N R 35 E W M.

Chains

mound, as per instructions.  
 80.00 Set Sec. post Cor. for Secs. 28, 29, 32 & 33. Drove charred stake; dug pits & raised mound, as per instructions.  
 Land; gently rolling.  
 Grass; good.  
 Soil; good 2nd rate.

E. on random bet. Secs. 28 & 33.

40.00 Set temp.  $\frac{1}{4}$  Sec. post.  
 40.75 Road, course N.W.  
 80.47 Intersect N. & S. line, 10 lks. S. of post, from which, I run  
 S.89°56'W. on true line.  
 40.23 Set  $\frac{1}{4}$  Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.

80.47 To post Cor.  
 Land; gently undulating.  
 Grass; good.  
 Soil; good 2nd rate.

N. bet. Secs. 28 & 29.

Var.21°E.

30.60 Road, course N.W.  
 40.00 Set  $\frac{1}{4}$  Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.  
 64.67 Spring branch, 5 lks. wide, course N.W.  
 80.00 Set post Cor. for Secs. 20, 21, 28 & 29. Drove charred stake; dug pits & raised mound as per instructions.  
 Land; gently rolling.  
 Grass; good.  
 Soil; 2nd rate.

E. on random bet. Secs. 21 & 28.

40.00 Set temp.  $\frac{1}{4}$  Sec. post.