

Subdivisional Lines, T 6 N R 35 E W M.

Chains	W. on random bet. Secs. 30 & 31.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.78	Intersect N. & S. line, 18 lks. S. of post, from which, I run S. $89^{\circ}52'E.$, on true line.
39.78	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.
79.78	To post Cor. Land; gently rolling. Soil; 2nd rate.
N. bet. Secs. 29 & 30.	
Var. $21^{\circ}E.$	
14.11	Spring branch, course N.W.
40.00	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.
57.50	Spring branch, course N.W.
80.00	Set post Cor. for Secs. 19, 20, 29 & 30. Drove charred stake; dug pits & raised mound, as per instructions. Land; level. Grass; good. Soil; 2nd rate.
E. on random bet. Secs. 20 & 29.	
9.32	Road, course N.W.
39.17	Road, course N.W.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
67.50	Spring branch, course N.W.
79.55	Intersect N. & S. line, 75 N. of post, from which, I run N. $89^{\circ}28'W.$ on true line.
39.77	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
79.55	To post Cor. Land; gently rolling. Soil; 2nd rate.