

Subdivisional Lines, T 6 N R 35 E W M.

Chains

W. on random line bet. Secs. 19 & 30.

23.00 Road, course N. of W.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

79.75 Intersect W. Tp. line, 45 lks. N. of post, from which, I
run
N.89°41'E. on true line.

39.75 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised
mound, as per instructions.

79.75 To post Cor.
Land; gently rolling.
Soil; 2nd rate.

N. bet. Secs. 19 & 20.

Var.21°E.

40.00 Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised
mound, as per instructions.

80.00 Set post Cor. for Secs. 17, 18, 19 & 20. Drove charred
stake; dug pits & raised mound, as per instructions.
Land; gently rolling.
Soil; 2nd rate.

E. on random line bet. Secs. 17 & 20.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

57.19 Road, course N.

79.68 Intersect N. & S. line, 38 lks. N. of post, from which, I
run W. on true line.

39.84 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised
mound, as per instructions.

79.65 To post Cor.
Land; gently rolling.
Soil; 2nd rate.

W. on random line bet. Secs. 18 & 19.

40.00 Set temp. $\frac{1}{4}$ Sec. post.