

## Subdivisional Lines, T 6 N R 36 E W M.

<p>Chains</p> <p>40.00</p> <p>79.92</p> <p>39.96</p> <p>79.92</p>	<p>E. on random bet. Secs. 15 &amp; 22.</p> <p>Set temp. <math>\frac{1}{4}</math> Sec. post.</p> <p>Intersect N. &amp; S. line, S. of post, 32 lks., from which, I run S.89°46'W. on true line.</p> <p>Set <math>\frac{1}{4}</math> Sec. post. Drove charred stake; dug pits &amp; raised mound, as per instructions.</p> <p>To post Cor. Land; rolling. Grass; good. Soil; good 2nd rate.</p>
<p>40.00</p> <p>52.50</p>	<p>N. bet. Secs. 15 &amp; 16.</p> <p style="text-align: right;">Var.21°E.</p> <p>Set <math>\frac{1}{4}</math> Sec. post. Drove charred stake; dug pits &amp; raised mound, as per instructions.</p> <p>Intersect State Bdy. Line, 16 chs. &amp; 65 lks. W. of Mile post No. 32. Set post Cor. for fractional Secs. 15 &amp; 16. Drove charred stake; dug pits &amp; raised mound, as per instructions. Land; rolling. Grass; good. Soil; good 2nd rate.</p>
<p>40.00</p> <p>80.00</p>	<p>N. bet. Secs. 32 &amp; 33.</p> <p style="text-align: right;">Var.21°E.</p> <p>Set <math>\frac{1}{4}</math> Sec. post. Drove charred stake; dug pits &amp; raised mound, as per instructions.</p> <p>Set post Cor. for Secs. 28, 29, 32 &amp; 33. Drove charred stake; dug pits &amp; raised mound, as per instructions. Land; rolling. Grass; good. Soil; 2nd rate.</p>