

Subdivisional Lines, T 6 N R 36 E W M.

| | |
|--------|---|
| Chains | N. bet. Secs. 29 & 30. |
| | Var. 21° E. |
| 40.00 | Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions. |
| 80.00 | Set post Cor. for Secs. 19, 20, 30 & 29. Drove charred stake; dug pits & raised mound, as per instructions. |
| | Land; gently rolling. |
| | Grass; good. |
| | Soil; good 2nd rate. |
| <hr/> | |
| | E. on random bet. Secs. 20 & 29. |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. post. |
| 79.90 | Intersect N. & S. line at post, from which, I run |
| | W. on true line. |
| 39.95 | Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions. |
| 79.90 | To post Cor. |
| | Land; rolling gently. |
| | Grass; good. |
| | Soil; 2nd rate. |
| <hr/> | |
| | W. on random bet. Secs. 19 & 30. |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. post. |
| 79.85 | Intersect N. & S. Tp. line, 22 lks. N. of post, from which, |
| | I run |
| | N. 89° 50' E. on true line. |
| 39.85 | Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions. |
| 66.35 | Rail fence, or leave field. |
| 75.00 | Creek, course N.W. |
| 79.85 | To post Cor. |
| | Land; gently rolling. |
| | Grass; good. |
| | Soil; 2nd rate. |