

Exterior Lines, T 6 N R 37 E W M.
As surveyed by Odell & Lewsi, U.S. Deputy Surveyors,
Under Contract No. 110,
Dated Feb. 7th, 1865.

Chains

N. on E. Bdy. of Sec. 36.

Var. 21° E.

40.00 Made Cor. for $\frac{1}{4}$ Sec. on yew tree, 2 ins. diam., from which

A fir, 20 ins. diam., brs. S. 47° E., 12 lks. dist..

A yew, 8 ins. diam., brs. S. 38° W., 25 lks. dist.

80.00 Set a post Cor. for Secs. 25, 36, 31 & 30, on side of

Butte, from which

A fir, 20 ins. diam., brs. S. 12° E., 80 lks.

A " 3 " " " S. 50° 30' W., 24 lks.

A " 10 " " " N. 24° 30' E., 50 lks.

A larch, 14 " " " N. 44° W., 51 lks.

This line passes through excellent timber, fir, larch,
spruce and pine.

Undergrowth same with willow & maple.

Soil; 1st rate.

N. on E. Bdy. of Secs. 25

Var. 20° E.

4.00 Leave timber.

32.00 Summit of ridge.

Var. 17° E.

40.00 Set $\frac{1}{4}$ Sec. post Cor. Deposited marked stone & raised mound
of stone, as per instructions.

80.00 Made Cor. on fir, 4 ins. diam., for Secs. 19, 30, 24 & 25,
in thick growth of fir timber, small growth, on steep
hillside facing N.E., from which

A fir, 4 ins. diam., brs. S. 40° W., 6 lks.

A " 3 " " " S. 50° E., 5 "

A " 4 " " " N. 20° W., 10 "

A " 3 " " " N. 10° E., 8 "

This line passes over high ridge, bald on S., on N.E. some
timber. Course of ridge W. of N.

I was unable to trace this line further by reason of a
severe storm of wind, rain, hail and snow, compelling
us to descend to the valley. The distance from our camp