

Subdivisional Lines, T 6 N R 37 E W M.

Chains	
	E. on random bet. Secs. 24 & 25.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.27	Intersect Tp. Line, 30 lks. S. of Cor. for Secs. 19, 24, 25 & 30, from this Cor., I run S.89°46'W. on true line bet. Secs. 24 & 25.
1.77	Summit of ridge.
34.00	Bottom of gulch, falls N.E. Ascend.
40.14	Set post for $\frac{1}{4}$ Sec. Cor., in mound with pits.
45.10	Enter timber.
62.00	Top of divide bet. Cottonwood and Mill Creeks.
78.00	Timber road, N.W. & S.E.
80.27	To Cor. Mountainous. Timber; pine, fir & spruce.
	N. bet. Secs. 23 & 24. Var. 20°E.
2.50	Timber road, N.W. & S.E. Ascend.
28.00	Summit of ridge. Descend.
40.00	Set post for $\frac{1}{4}$ Sec. Cor., from which A red fir, 12 ins. diam., brs. N.80°E., 64 lks. dist. A " " 16 " " " N.65°W., 52 " "
50.20	Timber road, E. & W.
76.00	Leave timber.
80.00	Set post in mound with pits for Cor. to Secs. 13, 14, 23 and 24. Land; mountainous. Timber; pine, fir & tamarack.
	E. on random line bet. Secs. 13 & 24.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.