

## Subdivisional Lines, T 6 N R 37 E W M.

Chains	N. bet. Secs. 28 & 29.  Var. 21°E.
24.00	Cross ridge, 500 ft., falls N.W.
40.00	Set stone, 8 x 16 x 24, mound, of stone, for $\frac{1}{4}$ Sec. Cor.
80.00	Set stone, 4 x 24 x 30, mound & pits, for Cor. to Secs. 20, 21, 28 & 29.  Land; very hilly. No timber. Good grass.
	E. on random line bet. Secs. 21 & 28..
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.30	Intersect N. & S. line, 30 lks. S. of Cor. for Secs. 21, 22, 27 & 28, from which Cor., I run S. 89°47'W. on true line bet. Secs. 21 & 28.
39.65	Set post & marked stone, mound & pits, for $\frac{1}{4}$ Sec. Cor.
41.00	Cross ridge.
42.50	Cross road.
79.30	The Cor. for Secs. 20, 21, 28 & 29.  Land; hilly. No timber. Good grass.
	N. bet. Secs. 20 & 21.  Var. 21 $\frac{1}{2}$ °E.
21.50	Cross road, valley to timber.
24.00	Cross ridge.  Descend.
40.00	Set stone, 10 x 12 x 14, for $\frac{1}{4}$ Sec. Cor.
51.80	Deep canyon creek, 10 lks. wide, flows W.  Ascend.
55.50	Grade road, E. & W.
80.00	Set stone, 6 x 8 x 13, mound & pits, for Cor. to Secs. 16, 17, 20 & 21.  Land; mountainous. Small timber on creeks.