

## Subdivisional Lines, T 6 N R 37 E W M.

Chains	E. on random line bet. Secs. 16 & 21.
40.00	Set stone for temp. $\frac{1}{4}$ Sec. Cor.
79.56	Intersect N. & S. line, 49 lks. N. of Cor. for Secs. 15, 16, 21 & 22, from which Cor., I run N.89°39' W. on true line bet. Secs. 16 & 21.
39.78	Set stone, 2 x 6 x 15, mound of stone, for $\frac{1}{4}$ Sec. Cor.
56.41	Cross dry gulch.
65.00	Cross ridge.
79.56	The Cor. of Secs. 16, 17, 20 & 21. Land; hilly. No timber. Good grass.
	N. bet. Secs. 16 & 17. Var.21 $\frac{1}{2}$ °E.
11.50	Summit of ridge. Descend.
13.00	Cross rail fence, E. & W.
40.00	Set stone, 15 x 17 x 20, mound & pits, for $\frac{1}{4}$ Sec. Cor.
52.50	Intersect N. Bdy. of State, 16.05 chs. W. of 37 M. post. Set stone, 12 x 14 x 18, for Cor. to fractional Secs. 16 and 17. Land; hilly. No timber. Good grass. Oct.23, 1872.
	N. bet. Secs. 31 & 32. Var.21 $\frac{1}{2}$ °E.
10.00	Road to timber.
30.60	Cross fence J. Duer's field.
40.00	Set post, mound & pits for $\frac{1}{4}$ Sec. Cor.
46.00	W. Duer's granary, 50 lks. W.
62.75	Cross fence and leave field.
80.00	Set post, mound & pits for Cor. to Secs. 29, 30, 31 & 32. Soil; good. No timber. Good grass.