

Resurvey of the W. Bdy. of T 6 N., R. 39 E.

Chains		Feet												
	$\frac{1}{4}$ S18 1932 from which A fir, 10 ins. diam., brs. N. 36° E., 15 lks. dist., marked $\frac{1}{4}$ S 18 B T. A fir, 14 ins. diam., brs. S. 45° E., 27 lks. dist., marked $\frac{1}{4}$ S 18 B T. Continue to desc. 245 ft. over N. slope.													
45.10	Creek, 6 lks. wide, course W.; thence over flat.													
46.32	Intersect the Oregon and Washington boundary at the proportionate point for the closing cor. Set an iron post, 3 ft. long, 3 ins. diam., 27 ins. in the ground, for closing cor. of Tps. 6 N., Rs. 38 and 39 E., with brass cap marked													
	<table border="1" style="margin: auto;"> <tr><td>W</td><td>N</td></tr> <tr><td>S18</td><td>S13</td></tr> <tr><td>R38E</td><td>R39E</td></tr> <tr><td>T6N</td><td></td></tr> <tr><td>C</td><td>C</td></tr> <tr><td>1932</td><td></td></tr> </table> from which A fir, 9 ins. diam., brs. S. 32° E., 11 lks. dist., marked T 6 N R 39 E S 13 B C B T. A fir, 10 ins. diam., brs. S. 63° W., 33 lks. dist., marked T 6 N R 38 E S 18 B C B T. From this point the 46 mile monument on the Oregon and Washington Bdy., brs. N. 89° 49' W., 60.88 Chs. dist., previously described.	W	N	S18	S13	R38E	R39E	T6N		C	C	1932		
W	N													
S18	S13													
R38E	R39E													
T6N														
C	C													
1932														
	Land; mountainous Soil; sandy loam, rocky; 3rd rate. Timber; fir, pine, spruce and tamarack. Undergrowth, huckleberry, salal, willow, vinemaple, rose, mountain laurel, mountain mahogany, alder and Oregon grape.													
	Subdivisional Lines of T 6 N R 38 E., W.M. As surveyed by George Williams, U.S. Deputy Surveyor Under Contract No. 176, Dated July 20, 1872. Commenced, Oct. 5, 1872													
	Begin at the cor. for Secs. 1, 2, 35 & 36, on the S. Bdy. of the Tp., run N. bet. Secs. 35 & 36. Var. 21° 45' E.													
	Descend ridge													
40.00	Set stone, 24 x 6 x 6, and post in mound of earth with pits for $\frac{1}{4}$ Sec. Cor. on steep hill side, face N.E.													
63.00	Creek, 2 lks. wide, falls N.W. 200 lks., Ascend													
80.00	Set post for Cor. to Secs. 25, 26, 35 & 36, on side hill													