

Subdivisional Lines of T 6 N R 38 E., W.M.

Chains		Feet
39.80	Set post and mark stone in mound and pits for $\frac{1}{4}$ Sec. Cor.	
70.00	Enter timber.	
73.20	Creek, falls N.W., 6 lks. wide,	
79.60	The cor. for secs. 13, 14, 23 & 24.	
	Land; hilly and rocky.	
	Timber; scanty, fir, pine, tamarack and willow.	
<hr/>		
	N. bet. Secs. 13 & 14	
		Var. 21° E.
	Descend	
3.50	Creek, falls N.W., 18 lks. wide. Ascend	
25.50	Ridge and descend	
40.00	Set post and mark stone in mound with pits for $\frac{1}{4}$ Sec. Cor.	
42.00	Ascend	
52.10	Intersect State Line, 16.20 lks W. of the mound for 46	
	miles.	
	I set post and marked stone and raised mound of stone	
	for Cor. to Fractional Secs. 13, & 14.	
	Land; mountainous. and rocky	
	Timber; fir, pine, tamarack and spruce, cottonwood, Birch,	
	and alder in creek bottom.	
		Oct. 7, 1872.
<hr/>		
	N. bet. Secs. 34 & 35	
		Var. 23° E.
	Descend	
15.00	Sharp spur, falls W. 20 ft.	
20.00	Gulch, falls W. 200 ft.	
27.00	Spur, falls W. 250ft	
40.00	Set post on sharp rocky backbone, in mound of rock for	
	$\frac{1}{4}$ Sec. Cor.	
	A red fir, 7 ins. diam. brs. N. 10° E., 270 lks. dist.	
52.00	Bottom of gulch, 400 ft. and spring branch 2 lks. wide,	
	flows W. Ascend	
80.00	Set post and marked stone mound with pits for cor. to	
	secs. 26, 27, 34 & 35.	