

Subdivisional Lines of T 6 N R 38 E., W.M.

Chains		Feet
	Timber, fir, spruce, pine and tamarack.	
	<hr/>	
	E. on a random line bet. Secs. 27 & 34	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. temp.	
79.70	Intersect N. and S. line, 48 lks. N. of the Cor. for Secs, 26, 27, 34 & 35, from which Cor. I run	
	N. $89^{\circ} 39'$ W. on a true line bet. Secs. 27 & 34	
11.30	Gulch, falls N. Ascend	
22.00	Leave spur and descend	
39.85	Set post and mark stone in mound with pits on steep hill side, face N.E.	
52.00	Summit of sharp ridge, about 750ft.	
57.00	Enter timber	
79.70	The Cor. for Secs. 27, 28, 33 & 34.	
	<hr/>	
	N. bet. Secs. 27 & 28	
		Var. $20^{\circ} 10'$ E.
13.00	Gulch, falls W.	
40.00	Set post for $\frac{1}{4}$ Sec. cor. from which	
	A fir, 6 ins. diam. brs. N. 21° E., 26 lks. dist.	
	A fir, 20 ins. diam. brs. S. 40° W., 80 lks. dist.	
73.50	Cross spur and descend	
80.00	Set post for cor. to secs. 21, 22, 27 & 28	
	A pine, 15 ins. diam. brs. S. 43° W., 82 lks. dist.	
	A fir, 18 ins. diam. brs. W. 62° E., 110 lks. dist.	
	A fir, 6 ins. diam. brs. N. 20° W., 8 lks. dist.	
	Land; mountainous	
	Timber; pine, fir, spruce and tamarack.	
	<hr/>	
	E. on random line bet. Secs. 22 & 27	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.66	Intersected N. and S. 49 lks. N. of the Cor. for Secs. 22, 23, 26 & 27, from which cor I run	
	N. $89^{\circ} 39'$ W. on a true line bet. Secs. 22 & 27	
40.33	Set stone and marked stone with pits for $\frac{1}{4}$ Sec. Cor.	
45.43	Enter timber.	