

Subdivisional Lines of T 6 N R 38 E., W.M.

Chains		Fee
54.00	Enter timber	
57.00	Heavy gulch spring branch, 10 lks. wide Ascend	
80.60	The cor. for Secs. 29, 30, 31 & 32 Oct. 14th, 1872.	
<hr/>		
	N. bet. Secs. 29 & 30 Var. 21° E.	
	Descend	
28.00	Heavy gulch, 800 ft.	
30.00	Branch, 10 lks. wide, W. 11½° E.	
31.00	Ascend	
40.00	Set post for ¼ Sec. Cor., from which A pine, 14 ins. diam. brs. S. 45° W., 21 lks. dist. A pine, 26 ins. diam. brs. N. 50° E., 38 lks. dist.	
80.00	Set post for the cor. to Secs. 19, 20, 29 & 30 A pine, 15 ins. diam. brs. S. 5° E., 20 lks. dist. A pine, 10 ins. diam. brs. S. 36° W., 92 lks. dist. A pine, 8 ins. diam. brs. N. 23 lks. 112 lks. dist. A fir, 15 ins. diam. brs. N. 72° E., 73 lks. dist.	
	Land; mountainous	
	Timber, pine, fir, and tamarack.	
<hr/>		
	Eo on a random line bet. Secs. 20 & 29	
40.00	Set post for temp. ¼ Sec. Cor.	
80.20	Intersect N. and S. line, 21 lks. S. of the cor. of Secs. 20, 21, 28 & 29, from this cor. I run S. 89° 51' W. on true line bet. Secs. 20 & 29	
9.55	Creek, 6 lks. wide, flows W.	
9.70	Wood Road, N. and S.	
29.60	Ridge, 250 ft., falls N. Descend	
40.10	Set post for ¼ Sec. Cor., from which A fir, 8 ins. diam. brs. S. 1 lks. dist. A fir, 7 ins. diam. brs. N. 3° E., 11 lks. dist.	
61.20	Wood road, N. and S.	
61.30	Log Cabin, 20 ft. S.	