

Subdivisional Lines of T 6 N R 38 E., W.M.

Chains		Feet
62.00	Henry's Creek, flows N., 16 lks. wide Ascend	
80.20	The cor. for Secs. 19, 20, 29 & 30 Land; mountainous.	
W. on random line bet. Secs. 19 & 30		
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor	
80.43	Intersect W. Bdy. of Tp. 30 lks. S. of the Cor. for Secs. 19, 24, 25 & 30, from this cor. I run S. $89^{\circ} 47'$ E. on true line bet. Secs. 19 & 30	
7.43	Leave timber	
26.04	Spr. branch, 1 lk. wide, runs N.W.	
40.21	Set post for $\frac{1}{4}$ Sec. Cor. from which A fir, 10 ins. diam. brs. S. 45° E., 8 lks. dist. A fir, 6 ins. diam. brs. N. 20° W., 15 lks. dist.	
Descend		
80.43	The cor. for secs. 19, 20, 29 & 30	
Oct. 15th, 1872.		
N. bet. Secs. 19 & 20		
Var. 20° E.		
Descend		
40.00	Set post for $\frac{1}{4}$ Sec. Cor., from which A fir, 14 ins. diam. brs. S. 8° E., 14 lks. dist. A fir, 10 ins. diam. brs. W. 10° W., 27 lks. dist.	
63.00	Enter old chopping	
65.23	Mill Cr., 50 lks. wide, runs W.	
66.41	Road Walla Walla and Saw mill and timber	
72.50	Ascent	
74.00	Spring, 5 lks. W. of line	
80.00	Set post for the cor. to Secs. 17, 18, 19 & 20 A fir, 16 ins. diam. brs. N. 45° W., 67 lks. dist. A fir, 5 ins. diam. brs. S. 44° E., 36 lks. dist. A fir, 24 ins. diam., brs. S. 6° W., 95 lks. dist.	
Mountains, timber, pine, fir and alder & etc.		