

Subdivisional Lines, T 6 N R 39 E W M.

Chains	<p>Land; mountainous.</p> <p>Soil; sandy loam; rocky, 3rd rate.</p> <p>Timber; fir, pine, spruce & tamarack.</p> <p>Undergrowth; alder, huckleberry, mountain laurel, mountain ash, salal, vinemaple, Oregon Grape, rose & buck brush.</p> <hr/> <p>W., on true line bet. Secs. 30 & 31.</p> <p>20.00 Descend 85 ft. over NW. slope, through timber & brush.</p> <p>22.25 Ravine, course NW. asc. 140 ft. over NE. slope.</p> <p>13.75 Ridge spur, slopes NW.; desc. 525 ft. over W. slope.</p> <p>14.26 Dim trail, brs. NW. & SE.</p> <p>30.00 Ravine, course NW.; asc. 30 ft. over NE. slope.</p> <p>30.43 Intersect the W. Bdy. of the Tp.</p> <p>Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, for Closing Cor. of Secs. 30 & 31, with brass cap marked</p> <div style="text-align: center;"> <table border="0"> <tr> <td>T6N</td> <td> </td> <td>T6N</td> </tr> <tr> <td>S30</td> <td> </td> <td>S30</td> </tr> <tr> <td></td> <td> </td> <td>CC</td> </tr> <tr> <td></td> <td> </td> <td>S31</td> </tr> <tr> <td>R38E</td> <td> </td> <td>R39E</td> </tr> <tr> <td></td> <td> </td> <td>1932</td> </tr> </table> </div> <p>from which</p> <p>A fir, 10 ins. diam., brs. N. 67° E., 55 lks. dist., marked T 6 N R 39 E S 30 C C B T.</p> <p>A fir, 40 ins. diam., brs. S. 65$\frac{1}{2}$° E., 37 lks. dist., marked T 6 N R 39 E S 31 C C B T.</p> <p>From this point the Cor. of Secs. 25 & 36 only, T 6 N R 38 E., previously described, brs. S. 4° 15' E., 29 lks. dist.</p> <p>Land; mountainous.</p> <p>Soil; sandy loam, rocky, 3rd rate.</p> <p>Timber; fir, pine, spruce, tamarack & yew.</p> <p>Undergrowth; huckleberry, alder, salal, rose, Oregon grape, buck brush, mountain laurel & vinemaple.</p> <hr/> <p>Thence from the Cor. of Secs. 29, 30, 31 & 32.</p> <p>N. 0° 05' W., bet. Secs. 29 & 30.</p> <p>Along rolling W. slope, through timber & brush.</p>	T6N		T6N	S30		S30			CC			S31	R38E		R39E			1932
T6N		T6N																	
S30		S30																	
		CC																	
		S31																	
R38E		R39E																	
		1932																	