

Subdivisional Lines, T 6 N R 39 E W M.

Chains											
	West non-true line bet. Secs. 19 & 30.										
	Desc. 325 ft. over broken NW. slope, through timber & under- brush.										
23.80	Bottom of descent, brs. N. & S.; thence along N. slope.										
27.00	Desc. 160 ft. over NW. slope.										
36.28	Intersect the W. Bdy. of the Tp.										
	Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, for Closing Cor. of Secs. 19 & 30, with brass cap marked										
	<table border="1" style="margin-left: auto; margin-right: auto;"> <tr> <td>T6N</td> <td>T6N</td> </tr> <tr> <td>S24</td> <td>S19</td> </tr> <tr> <td></td> <td>S30</td> </tr> <tr> <td>R38E</td> <td>R39E</td> </tr> <tr> <td></td> <td>1932</td> </tr> </table>	T6N	T6N	S24	S19		S30	R38E	R39E		1932
T6N	T6N										
S24	S19										
	S30										
R38E	R39E										
	1932										
	from which										
	A fir, 12 ins. diam., brs. N. 25° E., 53 lks. dist., marked T 6 N R 39 E S 19 C C B T.										
	A fir, 10 ins. diam., brs. S. 12° E., 22 lks. dist., marked T 6 N R 39 E S 30 C C B T.										
	From this point the Cor. of Secs. 24 & 25 only, of T 6 N R 38 E., brs. S. 4° 15' E., 250 lks. Dist., previously de- scribed.										
	Land; mountainous.										
	Soil; sandy loam, rocky, 3rd rate.										
	Timber; fir, pine, spruce & tamarack.										
	Undergrowth; huckleberry, alder, salal, rose, vinemaple, Oregon grape, buck brush, fern & syringa.										
	N. 0° 05' W., bet. Secs. 19 & 20.										
	Asc. 75 ft. over gradual SW. slope, through timber & brush										
5.90	Spur, slopes W.; desc. 15 ft. over NW. slope.										
9.80	Bottom of descent, brs. E. & W.; asc. 110 ft. over SW. slope.										
18.60	Ridge spur, slopes NW.; desc. 240 ft. over NE. slope.										
30.85	Large boulder, 20 x 20 x 20 ft. above ground, on line; con- tinue to desc. 410 ft. over N. slope.										
40.00	Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for $\frac{1}{2}$ Sec. Cor., with brass cap marked										