

## Subdivisional Lines, T 6 N R 39 E W M.

Chains

S.89°49' E. along the Oregon &amp; Washington Bdy.

11.83 Mid point on the N. Bdy. of Sec. 17.

Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for  $\frac{1}{4}$  Sec. Cor. of Sec. 17 only, with brass cap marked

$$\frac{WN}{\frac{1}{4} S 17}$$

1932

from which

A fir, 10 ins. diam., brs. S.48°W., 51 lks. dist., marked  $\frac{1}{4}$  S 17 B T.

A fir, 14 ins. diam., brs. S.81°W., 57 lks. dist., marked  $\frac{1}{4}$  S 17 B T.

To complete the survey of Sec. 18, I go to the Closing Cor. of Tps. 6 N., Rs. 38 & 39 E., and run

S.89°49' E. along the Oregon &amp; Washington Bdy.

5.76 40.00 chs. in departure W. of the Closing Cor. of Secs. 17 and 18.

Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for  $\frac{1}{4}$  Sec. Cor. of Sec. 18 only, with brass cap marked

$$\frac{WN}{\frac{1}{4} S 18}$$

1932

from which

A fir, 14 ins. diam., brs. S.37°E., 23 lks. dist., marked  $\frac{1}{4}$  S 18 B T.

A fir, 14 ins. diam., brs. S.59°W., 48 lks. dist., marked  $\frac{1}{4}$  S 18 B T.

## GENERAL DESCRIPTION.

Proviso

Fractional Township 6 North, Range 39 East is located entirely within the Umatilla National Forest. The general elevation of the Tp. is about 5000 ft. above sea level; the summit of the main divide or along the Skyline Road is about 1000 ft. higher. The elevation of the Round Butte Trail and of Paradise Ridge is about the same as along Skyline Road. The NW. Cor. of the Tp. is set at