

Exterior Bdy. of T. 7 S., R. 30 E., W.M.

Chains		Feet
	W. on N. Bdy. of Sec. 3	
		Var. 17° 30' E.
13.00	Ravine, course S.	
26.00	Top of ridge, brs. N. and S.	
34.00	Brook, 3 lks. wide, course S.	
40.00	Set basalt stone, 10 x 10 x 8, in a mound of stone for ¼ Sec. Cor.	
43.50	Top of ridge, brs. N. and S.	
51.50	Brook, 2 lks. wide, course S.	
58.00	Top of ridge, brs. N. and S.	
65.00	Ravine, course S.	
74.00	Top of ridge, brs. N. and S.	
80.00	Set a basalt stone, 10 x 10 x 10 ins. in a mound of stone for Cor. to Secs. 3, 4, 33 & 34. Land; broken hillside Soil; 3rd rate. Scattering Pine and Juniper timber.	
	W. on N. Bdy. of Sec. 4	
		Var. 20° 30' E.
4.50	Ravine, course S.W.	
7.50	Top of ridge, brs. N. and S.	
9.00	Brook, 2 lks. wide, runs S.	
15.00	Top of ridge, brs. N. and S.	
33.00	Brook, 3 lks. wide, course S.	
40.00	Set a basalt stone, 15 x 15 x 10 in a mound of stone for ¼ Sec. Cor.	
40.50	Top of ridge, brs. N. and S.	
53.00	Ravine, course S.	
59.00	Top of ridge, brs. N. and S.	
64.50	Ravine, course S.	
80.00	Set a basalt stone, 30 x 10 x 8 in mound of stone for Cor. to Secs. 4, 5, 32 & 33. Land; broken hillside Soil; 3rd rate, Scattering pine and juniper, some mahogany and pine undergrowth	