

## Exterior Lines of T. 7 S., R. 30 E., W.M.

Chains		Feet
	W. on N. Bdy. of Sec. 5 Var. 18° E.	
5.00	Top of ridge, brs. N. and S.	
23.75	Ravine, course S.	
26.00	Top of ridge, brs. N. and S.	
37.00	Ravine, course S.	
40.00	Set a basalt stone, 12 x 12 x 8 in mound of stone for $\frac{1}{4}$ Sec. Cor.	
42.50	Top of ridge, brs. N. and S.	
58.00	Brook, 3 lks. wide, runs S.	
77.00	Top of ridge, brs. N. and S.	
80.00	Set a basalt stone, 14 x 10 x 7 and dug pits for Cor. to Secs. 5, 6, 31 & 32. Land; broken on hillside Soil; 3rd rate. Scattering pine and juniper.	
	W. on N. Bdy. of Sec. 6. Var. 20° 30' E.	
7.00	Brook, 6 lks. wide, runs S.	
10.00	Top of ridge, brs. N. and S.	
40.00	Set a basalt stone, 16 x 9 x 8 in a mound of stone for $\frac{1}{4}$ Sec. Cor.	
48.00	Ravine, course S.E.	
64.00	Top of ridge brs. N. and S.	
66.00	Ravine, course S.	
71.00	Top of ridge, brs. N. and S.	
74.00	Intersect W. Bdy. of Tp. at Cor. to Tps. 6 & 7 S., Rs. 29 and 30 E. Land; broken hillside Soil; 3rd rate. Scattering Juniper and Pine,	