

## Exterior Lines of T. 6 S., R. 29 E., W.M.

Chains		Feet
	Pine and Tamarack.	
	<hr/>	
	N. on E. Bdy of Sec. 12	
		Var. 17° 30' E.
40.00	Set a post for $\frac{1}{4}$ Sec. Cor. from which,	
	A Pine, 8 ins. in diam. brs. N. 41° E., 19 lks. dist.	
	A Pine, 8 ins. in diam. brs. S. 68° W., 26 lks. dist.	
80.00	Set a post for Cor. to Secs. 1, 6, 7 & 12, from which	
	A Pine, 18 ins. in diam. brs. S. 37° E., 10 lks. dist.	
	A Pine, 30 ins. in diam. brs. S. 55° W., 70 lks. dist.	
	A Pine, 40 ins. in diam. brs. N. 67° W., 50 lks. dist.	
	A Pine, 20 ins. in diam. brs. N. 61° E., 58 lks. dist.	
	Land; gently rolling	
	Soil; good 2nd rate.	
	Heavy pine, fir & tamarack timber. Dense fir, Pine & Tamarack undergrowth.	
	<hr/>	
	N. on E. Bdy of Sec. 1	
		Var. 16° E.
40.00	Set a post for $\frac{1}{4}$ Sec. Cor., from which	
	A Fir, 10 ins. in diam. brs. S. 57° E., 48 lks. dist.	
	A Fir, 10 ins. in diam. brs. S. 87° W., 11 lks. dist.	
79.42	Intersect 1st stand., 1522 lks. E., Stand. Cor., to Secs.	
	35 & 36, T. 5 S. 29 E., where set a post for closing Cor.	
	from which,	
	A Pine, 18 ins. in diam. brs. N. 18° E., 132 lks. dist.	
	A Pine, 40 ins. in diam. brs. S. 18° W., 21 lks. dist.	
	A Pine, 12 ins. in diam. brs. S. 77° E., 132 lks. dist.	
	Land; gently rolling	
	Soil; 2nd rate.	
	Heavy pine timber. Undergrowth of Pine and fir.	
		June 12, 1881.
	<hr/>	