

## Exterior Lines of T. 7 S., R. 31 E., W.M.

Chains		Feet
	Scattering pine timber. Good bunch grass.	
	N. 89° 39' E. on a true line on N. Bdy. Sec. 4 Var. 20° 16' E.	
.50	Descen hill, brs. N. and S.	
40.00	Set a basalt stone, 24 x 14 x 3, in a mound of stone, for ¼ Sec. Cor.	
48.00	Creek, 4 lks. wide, course N.E. Foot of hill, brs. N.E. and S.W. Ascend hill, from creek	
62.50	Top of hill, brs. N. and S.	
80.00	Set a pine post for Cor. to Secs. 3, 4, 33 & 34, from which, A Fir, 28 ins. in diam. brs. N. 45° E., 13 lks. dist. A Fir, 8 ins. in diam. brs. N. 11° W., 57 lks. dist. A Fir, 34 ins. in diam. brs. S. 33° W., 63 lks. dist. A Fir, 36 ins. in diam. brs. S. 47° E., 19 lks. dist. Land; hilly and mountainous Soil; 2nd rate. Heavy fir and pine on E. 35 Chs. Balance scattering pine; good grass.	
	N. 89° 39' E. on a true line on N. Bdy of Sec. 3 Var. 16° 30' E.	
2.25	Creek, 20 lks. wide, runs. N. Foot of hill, brs. N. and S.	
2.75	Ascend hill, brs. N. and S.	
19.00	Top of hill, brs. E. & S.W.	
39.50	Ravine, course N.	
40.00	Set a pine post for ¼ Sec. Cor. A Pine, 40 ins. diam. brs. N. 43° E., 118 lks. dist. A Fir, 20 ins. diam. brs. S. 55° W., 29 lks. dist.	
79.25	Ravine, course N.	
80.00	Set a basalt stone, 22 x 10 x 6, in a mound of stone for	