

Exterior lines of T. 6 S., R. 31 E., W.M.

Chains		Feet
	Soil; 2nd rate. Heavy bunch grass.	
<hr/>		
	N. on E. Bdy. of Sec. 24 Var. 18° E.	
40.00	Set a basalt stone, 16 x 10 x 8, in a mound of stone for $\frac{1}{4}$ Sec. Cor.	
79.00	Ravine, course E.	
80.00	Set a basalt stone, 26 x 14 x 8, in a mound of stone, for Cor. to Secs. 13, 18, 19 & 24.	
	Land; rolling Soil; 2nd rate. Scattering pint timber on N. $\frac{1}{4}$; remainder open Heavy bunch grass.	
<hr/>		
	N. on E. Bdy. of Sec. 13 Var. 18° 45' E.	
26.45	Dry ravine, course N.W.	
40.00	Set a basalt stone, 18 x 12 x 7, in a mound of stone for $\frac{1}{4}$ Sec. Cor.	
55.60	Descend hill, brs. E. and W.	
61.80	Bridge creek, 20 lks. wide, runs W. Foot of hill brs. E. and W.	
63.40	Ascend hill, brs. E. and W.	
70.00	Top of hill, brs. E. and W.	
80.00	Set a fir post for Cor. to Secs. 7, 12, 13, 18, from which A Pine, 20 ins. in diam. brs. N. 37° E., 127 lks. dist. A Fir, 9 ins. in diam. brs. N. 45° W., 24 lks. dist. A Tamarack, 24 ins. diam. brs. S. 55° W., 69 lks. dist. A Pine, 16 ins. in diam. brs. S. 43° E., 70 lks. dist.	
	Land; hilly Soil; 2nd rate. Heavy pine and fir on N. $\frac{1}{4}$; and in ravine. Dense undergrowth of young Fir, Pine and willows.	