

Subdivisional Lines of T. 6 S., R. 31 E. W.M.

Chains		Feet
	distance across, where flag brs. S. 45° E., 150 lks. wide.	
	Thence N. on a true line	
	Ascend hill from river, brs. E. and W.	
40.00	Set a basalt stone, 22 x 18 x 9, in a mound of stone, for ¼ Sec. Cor.	
48.00	Top of hill, brs. E. and W.	
80.00	Set a basalt stone, 19 x 9 x 8, and dug pits for Cor. to Secs. 25, 26, 35 & 36.	
	Land; S. 48 Chs. hilly; N. 32 Chs. rolling	
	Soil; 2nd rate.	
	Scattering pine and S. ½.	
	<hr/>	
	E. on a random line bet. Secs. 25 and 36	
40.00	Set a temp. ¼ Sec. Cor.	
80.50	Intersect E. Bdy. of T., 190 lks. S. of Cor. to Secs. 25, 30, 31, 36, from which Cor. I run	
	S. 88° 39' W. on a true line bet. Secs. 25 & 36	
10.50	Top of hill, brs. N. and S.	
23.20	Ravine, course N.	
	Foot of hill, course N. and S.	
28.00	Trail, brs. N.W. and S.E.	
28.98	Ravine, course S.E.	
37.80	Top of hill, brs. N. and S.	
40.28	Set a basalt stone, 14 x 9 x 7, and erected mound of stone for ¼ Sec. Cor.	
80.50	To Cor. to Secs. 25, 26, 35 & 36	
	Land; E. 10 Chs., and W. 42.70 Chs. rolling; remainder hilly,	
	Soil; E. ½ 2nd rate; W. ½ good 2nd rate.	
	Scattering pine in ravine; remainder open.	
	Heavy bunch grass; sun flower.	
	<hr/>	
	N. bet. Secs. 25 & 26	
	Var. 18° 45' E.	
40.00	Set a basalt stone, 15 x 8 x 5, and erected mound of stone	