

Subdivisional Lines of T. 6 S., R. 31 E., W.M.

Chains		Feet
	S. 88° 43' W. bet. Sec. 29 and 32	
79.90	To Cor. to Secs. 29, 30, 31 & 32.	
	Land; rolling	
	Soil; 2nd rate, except river bottom level	
	Soil; good 2nd rate.	
	Scattering pine timber and Alder on river.	
	July 3, 1881	
	<hr/>	
	W. on a random line bet Sec. 30 & 31	
40.10	Set a temp. $\frac{1}{4}$ Sec. Cor.	
77.50	Intersect W. Bdy. of T., 174 lks. N. of Cor. to Secs. 25, 30, 31 & 36, from which Cor. I run	
	N. 88° 45' E. on a true line bet. Secs. 30 & 31	
16.50	To foot of hill, brs. N.W. and S.E.	
19.00	John Day river, 150 lks. wide, runs. N.W.	
	Offset N., thence 4 Chs E. on offset, thence on true line	
32.25	Brook, 2 lks. wide, runs N.	
	Foot of hill, brs. N.W. and S.E.	
37.50	Set a basalt stone, 24 x 12 x 12 for $\frac{1}{4}$ Sec. Cor., from which	
	A Yellow Pine, 24 ins. diam. brs. N. 49° W., 125 lks dist.	
	A " " 20 " " " S. 82° E., 160 " "	
64.75	Top of ridge, brs. N.W. and S.E.	
73.90	Creek, 15 lks. wide, runs S.E.	
77.50	To Cor. to Secs. 29, 30, 31, 32.	
	Land; hilly,	
	Soil; 2nd rate.	
	Heavy pine and fir on W. $\frac{1}{2}$ and E., 5 Chs.	
	Scattering pine on remainder. Undergrowth of young pine, fir and greasewood.	
	<hr/>	
	N. bet. Secs. 29 & 30	
	Var. 21° 45' E.	
20.50	Creek, 15 lks. wide, runs, S.W.	
24.50	Dry gulch, course S.E.	
40.00	Set a basalt stone, 14 x 10 x 5, and made mound of stone,	