

Exterior Lines, T 7 S R 32 E W M.
 As surveyed by Rufus S. Moore, U.S. Dept. Surveyor,
 Under Contract No. 382,
 Dates March 23, 1881.

Chains

W. on random line on N. Bdy. of Secs. 1, 2, 3, 4, 5 & 6;
 on N. Bdy. of Tp. 7 S R 32 E.
 At 6 miles, 1 ch. & 15 lks., I
 Intersect W. Bdy. 189 lks. N. of Cor. to Tps. 6 & 7, Rs. 31
 & 32 E.
 Run thence
 N. 89° 47' E. on true line on N. Bdy. of Sec. 6.

7.00 Dry gulch, course N.
 19.20 Top of hill, brs. N.E. & S.W.
 32.00 Descend hill, brs. N. & S.
 41.15 Set basalt stone, 20 x 12 x 6, in mound of stone, for $\frac{1}{4}$
 Sec. Cor.
 A yellow pine, 32 ins. diam., brs. S. 3° E., 65 lks. dist.,
 52.00 Ravine, course N. & S.
 Foot of hill & ascend from ravine.
 67.00 Top of ridge, brs. N. & S.
 77.60 Ravine, course N.E.
 81.15 Set basalt stone, 18 x 12 x 4, in mound of stone, for Cor.
 to Secs. 5, 6, 31 & 32, from which
 A yellow pine, 36 ins. diam., brs. S. 71° E., 75 lks.
 Heavy pine & fir on W. 15 chs.
 Scattering pine on remainder.

N. 89° 47' E. on N. Bdy. of Sec. 5
 Var. 19° E.

18.00 Ravine, course N.W.
 35.80 Top of ridge, brs. N.W. & S.E.
 40.00 Set yellow pine post, for $\frac{1}{4}$ Sec. Cor.
 A tamarack, 26 ins. diam., brs. N. 67° E., 25 lks. dist.
 A yellow pine, 36 ins. diam., brs. S. 43° E., 21 lks. dist.,
 47.50 Ravine, course N.
 80.00 Set yellow pine post, for Cor. to Secs. 4, 5, 32 & 33,
 from which
 A yellow pine, 22 ins. diam., brs. N. 30° E., 64 lks. dist.
 A tamarack, 26 ins. diam., brs. N. 42° W., 119 lks. dist.
 A yellow pine, 20 ins. diam., brs. S. 48° W., 103 lks. dist.
 A tamarack, 18 ins. diam., brs. S. 73° E., 71 lks. dist.