

Subdivisional Lines, T 6 S R 32 E W M.

Chains	<p>A fir, 24 ins. diam., brs. S.63°E., 36 lks. dist., marked T 7 S R 32 E S 3 B T.</p> <p>A pine, 34 ins. diam., brs. S.38°W., 19 lks. dist., marked T 7 S R 32 E S 4 B T.</p> <p>A pine, 24 ins. diam., brs. N.63°W., 100 lks. dist., marked T 6 S R 32 E S 33 B T.</p> <p>I run N. bet. Secs. 33 & 34. Var. 20°30'E.</p> <p>Descend.</p> <p>40.00 Set basalt stone, 15 x 13 x 4 ins., 10 ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face, from which A pine, 10 ins. diam., brs. S.85°E., 27 lks. dist., marked ¼ S B T. A pine, 8 ins. diam., brs. S.67°W., 63 lks. dist., marked ¼ S B T.</p> <p>80.00 Set basalt stone, 18 x 15 x 8 ins., 12 ins. in ground, for Cor. to Secs. 27, 28, 33 & 34, marked with 1 notch on S. and 3 notches on E. edges, from which A pine, 8 ins. diam., brs. N.23°E., 55 lks. dist., marked T 6 S R 32 E S 27 B T. A pine, 30 ins. diam., brs. S.47°E., 39 lks. dist., marked T 6 S R 32 E S 34 B T. A pine, 30 ins. diam., brs. S.30°W., 120 lks. dist., marked T 6 S R 32 E S 33 B T. A fir, 8 ins. diam., brs. N.6°W., 25 lks. dist., marked T 6 S R 32 E S 28 B T.</p> <p>Land; mountainous. Soil; 2nd rate. Densely covered with forests of pine, fir & tamarack timber, 80 chs. Undergrowth of small pine & balm, 80 chs.</p> <hr/> <p>E. on random line bet. Secs. 27 & 34. Var. 20½°E.</p> <p>5.50 Trail, course N.W. & S.E.</p>
--------	--