

## Exterior Lines, T 6 S R 33 E W M.

Chains	
	<p>marked T 6 S R 33 E S 24 B T.</p> <p>Land; mountainous.</p> <p>Soil; 3rd rate.</p> <p>Densely covered with forests of pine, fir, spruce &amp; tamarack, 80 chs.</p> <p style="text-align: right;">June 22, 1883.</p>
	<p>N. bet. Secs. 19 &amp; 24.</p> <p style="text-align: right;">Var. 19°40'E.</p> <p>Descend 200 ft.</p>
40.00	<p>A basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> on W. face, from which</p> <p>A pine, 8 ins. diam., brs. N.45°E., 4 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p> <p>A spruce, 8 ins. diam., brs. S.81°W., 6 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p>
53.26	Brook, 4 lks. wide, runs N.E.
77.50	Brook, 3 lks. wide, runs N.E.
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 18, 19, 13 &amp; 24, marked</p> <p style="text-align: center;">T 6 S S 18 on N.E.</p> <p style="text-align: center;">R 34 E S 19 on S.E.</p> <p style="text-align: center;">R 33 E S 24 on S.W. and</p> <p style="text-align: center;">S 13 on N.W. edges, with</p> <p style="text-align: center;">3 notches on N. &amp; S. edges, from which</p> <p>A pine, 10 ins. diam., brs. N.66°E., 26 lks. dist., marked T 6 S R 34 E S 18, B T.</p> <p>A pine, 11 ins. diam., brs. S.10°E., 17 lks. dist., marked T 6 S R 34 E S 19 B T.</p> <p>A tamarack, 10 ins. diam., brs. S.25°W., 76 lks. dist., marked T 6 S R 33 E S 24 B T.</p> <p>A pine, 10 ins. diam., brs. N.18°W., 41 lks. dist., marked T 6 S R 33 E S 13 B T.</p> <p>Land; mountainous.</p> <p>Soil; 2nd rate. Densely covered with forests of pine, fir, spruce and tamarack, 80 chs. Thick undergrowth of spruce and pine. 80 chs.</p>