

Exterior Lines, T 6 S R 33 E., W. M.

Chains	
	N. bet. Secs. 13 & 18. Var. 20° E.
5.00	Brook, 4 lks. wide, runs E.
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face, from which A fir, 24 ins. diam., brs. S. 40° W., 25 lks. dist., marked $\frac{1}{4}$ S B T. A tamarack, 18 ins. diam., brs. N. 23° E., 11 lks. dist., marked $\frac{1}{4}$ S B T.
57.50	Creek, 10 lks. wide, course N.W.
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 12, 13, 7 & 18, marked T 6 S S 7 on N.E. R 34 E S 18 on S.E. R 33 E S 13 on S.W. and S 12 on N.W. edges, with 2 notches on N. and 4 notches on S. edges, from which A spruce, 10 ins. diam., brs. N. 19° E., 32 lks. dist., marked T 6 S R 34 E S 7 B T. A spruce, 10 ins. diam., brs. S. 38° E., 31 lks. dist., marked T 6 S R 34 E S 18 B T. A spruce, 5 ins. diam., brs. S. 38° W., 14 lks. dist., marked T 6 S R 33 E S 13 B T. A tamarack, 30 ins. diam., brs. N. 44° W., 14 lks. dist., marked T 6 S R 33 E S 12 B T.
	Land; mountainous. Soil; 2nd rate. Densely covered with forests of pine, fir, spruce and tamarack, 80 chs.
	N. bet. Secs. 7 & 12. Var. 19 $\frac{1}{2}$ ° E.
1.50	Brook, 3 lks. wide, runs W. Ascend.
30.00	Ridge, 300 ft. high, course E. & W. Descend 250 ft.