

Subdivisional Lines, T. 6 S., R. 33 E., W. M.

Chains	
	N. bet. Secs. 25 & 26.
	Var. 20°E.
	Over gently rolling ground.
40.00	Set a fir post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face, from which A fir, 12 ins. diam., brs. S.25°W., 26 lks. dist., marked $\frac{1}{4}$ S B T. A spruce, 10 ins. diam., brs. S.75°E., 26 lks. dist., marked $\frac{1}{4}$ S B T.
	Gently descending.
73.00	Creek, 6 lks. wide, course W.
74.00	Trail, at foot of descent, course E. & W.
80.00	Set quartz stone, 16 x 8 x 8 ins., 10 ins. in ground, for Cor. to Secs. 23, 24, 25 & 26, marked with 2 notches on S. and 1 notch on E. edges, from which A pine; 10 ins. diam., brs. N.8°E., 39 lks. dist., marked T 6 S R 33 E S 24 B T. A pine; 8 ins. diam., brs. S.42°W., 75 lks. dist., marked T 6 S R 33 E S 26 B T. A pine; 11 ins. diam., brs. S.44°E., 29 lks. dist., marked T 6 S R 33 E S 25 B T. A pine, 8 ins. diam., brs. N.85°W., 50 lks. dist., marked T 6 S R 33 E S 23 B T.
	Land; rolling.
	Soil; 2nd rate.
	Densely covered with forests of pine, fir, spruce timber, partly deadened by fire, 80 chs.
	Thick undergrowth of small pine, fir & spruce, 80 chs.
	E. on random line bet. Secs. 24 & 25.
	Var. 20°E.
00.30	Spring branch, 3 lks. wide, course S.E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
	Thence descending hillside, course S.E.
79.70	Intersect E. Bdy. of Tp., at 18 lks. N. of Cor. to Secs. 19, 24, 25 & 30, which is a granite stone, 18 x 12 x 10